

L3 CARRIER
OVER-ALL TESTS AND ADJUSTMENTS OF AN L3 SYSTEM —
TERMINAL TO TERMINAL
GENERAL

1. GENERAL

1.01 This section and associated sections in this subdivision describe the tests and adjustments to be made on a terminal-to-terminal basis.

1.02 This section is reissued to show references to Plant Series section numbers in the associated sections.

1.03 Prior to making the terminal-to-terminal measurements, a sufficient number of tests and adjustments must have been made on the submaster and mastergroup equipment (Division 356) to insure correct operation of transmitting

and receiving terminal equipment. The equalization line-up of the high-frequency line must also have been completed.

1.04 Associated sections covering the terminal-to-terminal tests and adjustments are as follows:

359-078-501 — 308 KC Synchronizing Frequency Amplifier Output Check

359-078-502 — Check of Synchronization of 4 KC Frequency Supply Circuits

359-078-503 — Level Measurements and Adjustments at Receiving Terminal Equipments — Message