

**ALARM AND TIMING EQUIPMENT UNITS
ASSOCIATED WITH PERMANENT SIGNAL HOLDING TEST TRUNK
SELECTING AND CONCENTRATING EQUIPMENTS
EQUIPMENT DESIGN REQUIREMENTS
NO. 5 CROSSBAR SYSTEM**

1. GENERAL

1.001 This addendum supplements Section 819-753-150, Issue 6.

1.002 This addendum is issued to change the wording of list 1 and 2 of the auxiliary timing unit for announcement trunk, J23060G in accordance with SD-25870-01, Issue 17D.

4. EQUIPMENT

The following changes apply to Part 4 of the section:

Under J23060G

Change: List 1 To Read:

List 1 — Equipment and wiring for one auxiliary timing unit arranged for 400 announcement trunks and equipped for 100 per SD-25870-01, Fig. 4.

Change: List 2 To Read:

List 2 — Equipment and wiring required in addition to list 1 for operation for each additional 100 trunks per SD-25870-01, Fig. 4 (a maximum of three list 2).

Bell Telephone Laboratories, Incorporated

Dept 5614